DUROTECH INDUSTRIES
14, Essex Street, Minto, NSW 2566
Telephone: 61 2 9603 11 77
Fax: 62 2 9475 5059
Email: sales@durotechindustries.com.au
Web: www.durotechindustries.com.au

Attn:	**kal**
Company:	**Iconic Designs**
Address:	**test**
Specfication:	**test**
Email:	**kal@durotechindustries.com.au**
Date:	**21/01/2019**

Thank you for the opportunity to specify Durotech Waterproofing membranes for the above mentioned project. With this in mind we have pleasure in submitting our product specification to carry out works. The warranty will be in the form of a Materials Warranty.

Substrate Preparation & Treatment of Cracks: For Liquid applied membranes

1. All concrete, masonry should be cured for 28 days.
2. Surface to receive coating, sealant or liquid applied flashing material shall be sound, dry, clean and free of all dirt, dust, oil, grease, wax, tar, asphalt, mildew, mold, paint, sealers, coatings, curing agents, loose particles, laitance and other contaminants. The substrate must not contain any flaky/powdery cement or residues that may affect the membrane adhesion.
   Ensure that all protrusions have been removed.
3. Voids and honeycomb areas should be patched with a non-shrinking, quick setting grout. Allow the patched/ rendered areas to fully cure. Jack hammered areas should be filled to provide smooth substrate.
4. All surfaces shall be made free of defects which may telegraph and show through the coating.
5. Movement joints should be treated in the appropriate manner.
6. Allow substrate to dry completely.
7. Broom clean substrate.

Concrete finish shall be a light steel trowel followed by a fine hair broom, or equivalent finish. All surfaces shall be made free of defects which may telegraph and show through the coating.
Prior to applying membranes make sure that the substrate contains less than 5% moisture.

Treatment of Cracks for Liquid applied membranes

Cracks —Non Movement: Hairline cracks less than 1.5mm may be pre-treated with a 1mm detail coating of the specified DuroMastic membrane 150mm wide centered over the crack.

Movement cracks: Greater than 1.5mm shall be routed out, install a backer rod and fill with DuroFlex FC Polyurethane sealant then coat with a 1mm detail coat of the specified DuroMastic water based Polyurethane membrane.

Reinforcement Steel: In the event of exposed reinforcing steel, the exposed portions of steel shall be ground to expose clean, bright, metal and primed with a Duroproof Non Porous Primer.

Drainage: All drains shall be cleaned and operative. Drain flanges shall be recessed lower than the deck surface. The surface shall be sloped to the drain to Australian standard falls for positive drainage. Non Porous Primer is required if fittings are PVC or metal.

Substrate Moisture: The condition of "dry" shall be determined by moisture meter devise or fastening a rubber mat to the concrete deck for a minimum of six hours. The mat shall be located in an area exposed to the sun. After six hours (minimum), the surface beneath the rubber mat shall show minimal evidence of moisture or dampness. 12% moisture content or less is acceptable when using Duromastic Hibuild Epoxy Primers. Possible 2-3 coat epoxy priming process depending on moisture content and porosity of substrates.

Water Testing: When water testing, make sure it is carried out to the relevant Australian standard and allow for the membrane to dry prior to water testing. Allow membrane to dry after removing water. Ensure membrane is dry before applying further coatings or finishing with other coverings.

Refer to all technical data sheets and Application Instruction Manuals for further details prior to carrying out works.

Observations

Periodical observations can be carried out during the membrane application by applicator, however it is the responsibility of the builder to supervise and maintain the quality of the works. The applicator/ builder will inform Durotech should the need arise for an inspection by a Durotech representative.

Contractor Applicator

Durotech waterproofing systems must be applied by competent applicators who have a minimum of 5 years installing Durotech systems. A list of applicators can be provided to the builder upon request to the undersigned below.

Any alterations to the above product specification without approval from Durotech may void warranties.

Waterproofing System Recommendation on Fibre Cement Sheeting with artificial turf on surface.

Floor:

Product	Coverage	Coverage by Pack
Primer – Duromix WBE Hibuild	$5m^2/L$	20L Kit = $100m^2$
Detailing: Polyurethane Joint Sealant	1LM/100ml	600ml = 6LM
Membrane: Duromastic P15	$2L/m^2$ (2 coats min)	15L /$7.5m^2$
Screed		
Primer – Duromix WBE Hibuild	$5m^2/L$	20L Kit = $100m^2$
Detailing: Polyurethane Joint Sealant	1LM/100ml	600ml = 6LM
Membrane: Duromastic P15	$2L/m^2$ (2 coats min)	15L /$7.5m^2$

Planter Box:

Product	Coverage	Coverage by Pack
Primer – Duromix WBE Hibuild	$5m^2/L$	20L Kit = $100m^2$
Detailing: Polyurethane Joint Sealant	1LM/100ml	600ml = 6LM
Membrane: Duroproof PUM	$2L/m^2$ (2 coats min)	15L /$7.5m^2$

Membranes used must comply to AS4858, 2004.
Detailing Methodology to comply with AS465. 2, 2012.