14 Essex Street, P.O Box 5092, Minto, NSW 2566
+61 2 9603 1177
+61 2 9475 5059
sales@durotechindustries.com.au
www.durotechindustries.com.au
ABN: 33 738 594 170

Attn:	**tim quirk**
Company:	**idg architects**
Address:	**emu plains**
Specfication:	**Waterproofing system**
Email:	**kal@durotechindustries.com.au**
Date:	**1970-01-01**
Reference id:	**DTSPEC 19-10-035**

Thank you for the opportunity to specify Durotech Waterproofing membranes for the above mentioned project. With this in mind we have pleasure in submitting our product specification to carry out works. The warranty will be in the form of a Materials Warranty.

Substrate Preparation & Treatment of Cracks: For Liquid applied membranes

1. All concrete, masonry should be cured for 28 days.
2. Surface to receive coating, sealant or liquid applied flashing material shall be sound, dry, clean and free of all dirt, dust, oil, grease, wax, tar, asphalt, mildew, mold, paint, sealers, coatings, curing agents, loose particles, laitance and other contaminants. The substrate must not contain any flaky/powdery cement or residues that may affect the membrane adhesion.Ensure that all protrusions have been removed.
3. Voids and honeycomb areas should be patched with a non-shrinking, quick setting grout. Allow the patched/ rendered areas to fully cure. Jack hammered areas should be filled to provide smooth substrate.
4. All surfaces shall be made free of defects which may telegraph and showthrough the coating.
5. Movement joints should be treated in the appropriate manner.
6. Allow substrate to dry completely.
7. Broom clean substrate.

Concrete finish shall be a light steel trowel followed by a fine hair broom, or equivalent finish. All surfaces shall be made free of defects which may telegraph and show through the coating.
Prior to applying membranes make sure that the substrate contains less than 5% moisture.

Treatment of Cracks for Liquid applied membranes

Cracks —Non Movement: Hairline cracks less than 1.5mm may be pre-treated with a 1mm detail coating of the specified DuroMastic membrane 150mm wide centered over the crack.

Movement cracks: Greater than 1.5mm shall be routed out, install a backer rod and fill with DuroFlex FC Polyurethane sealant then coat with a 1mm detail coat of the specified DuroMastic water based Polyurethane membrane.

"This document, including any attached files, is strictly confidential and intended solely for the use of the individual or entity to which it is addressed. Durotech Industries prohibits the right to publish, copy, distribute or disclose any information contained in this document, or its attachments, by any party other than the intended recipient. If you have received this document in error please notify the sender and delete it from your system immediately. no employee or agent is authorised to conclude any binding agreement or make any representation on behalf of Durotech Industries. The views or opinions presented in this document are solely those of the author and do not necessarily represent those of Durotech Industries, except where the sender expressly, and with clear authority, states them to be the views of Durotech Industries. Durotech Industries accepts no liability for any loss or damage (direct or indirect or consequential) arising from the use of or in connection with this document and any attacchments and suggests that the recipient check this document and any attached files for the presence of viruses."

DUROTECH
Engineered Construction Chemicals
Made In Australia For Over 42 Years

14 Essex Street, P.O Box 5092, Minto, NSW 2566
+61 2 9603 1177
+61 2 9475 5059
sales@durotechindustries.com.au
www.durotechindustries.com.au
ABN: 33 738 594 170

Reinforcement Steel: In the event of exposed reinforcing steel, the exposed portions of steel shall be ground to expose clean, bright, metal and primed with a Duroproof Non Porous Primer.

Drainage: All drains shall be cleaned and operative. Drain flanges shall be recessed lower than the deck surface. The surface shall be sloped to the drain to Australian standard falls for positive drainage. Non Porous Primer is required if fittings are PVC or metal.

Substrate Moisture: The condition of "dry" shall be determined by moisture meter devise or fastening a rubber mat to the concrete deck for a minimum of six hours. The mat shall be located in an area exposed to the sun. After six hours (minimum), the surface beneath the rubber mat shall show minimal evidence of moisture or dampness. 12% moisture content or less is acceptable when using Duromastic Hibuild Epoxy Primers. Possible 2-3 coat epoxy priming process depending on moisture content and porosity of substrates.

Water Testing: When water testing, make sure it is carried out to the relevant Australian standard and allow for the membrane to dry prior to water testing. Allow membrane to dry after removing water. Ensure membrane is dry before applying further coatings or finishing with other coverings.

Refer to all technical data sheets and Application Instruction Manuals for further details prior to carrying out works.

Observations

Periodical observations can be carried out during the membrane application by applicator, however it is the responsibility of the builder to supervise and maintain the quality of the works. The applicator/ builder will inform Durotech should the need arise for an inspection by a Durotech representative.

Contractor Applicator

Durotech waterproofing systems must be applied by competent applicators who have a minimum of 5 years installing Durotech systems. A list of applicators can be provided to the builder upon request to the undersigned below.

Any alterations to the above product specification without approval from Durotech may void warranties.

Waterproofing System Recommendation on Fibre Cement Sheeting with artificial turf on surface.

"This document, including any attached files, is strictly confidential and intended solely for the use of the individual or entity to which it is addressed. Durotech Industries prohibits the right to publish, copy, distribute or disclose any information contained in this document, or its attachments, by any party other than the intended recipient. If you have received this document in error please notify the sender and delete it from your system immediately. no employee or agent is authorised to conclude any binding agreement or make any representation on behalf of Durotech Industries. The views or opinions presented in this document are solely those of the author and do not necessarily represent those of Durotech Industries, except where the sender expressly, and with clear authority, states them to be the views of Durotech Industries. Durotech Industries accepts no liability for any loss or damage (direct or indirect or consequential) arising from the use of or in connection with this document and any attacchments and suggests that the recipient check this document and any attached files for the presence of viruses."

JAS-ANZ
ISO 9001 Quality Certified System
ISO 14001 Environment Certified System
ISO 45001 Health and Safety Certified System

DUROTECH
Engineered Construction Chemicals
Made In Australia For Over 42 Years

14 Essex Street, P.O Box 5092, Minto, NSW 2566
+61 2 9603 1177
+61 2 9475 5059
sales@durotechindustries.com.au
www.durotechindustries.com.au
ABN: 33 738 594 170

Use Area

	Product	Coverage	MFT	Warranty
1	Internal below screed			
1.1	WBE hibuild epoxy primer 1st coat	80m2	.3	
1.3	Duromastic PUM 1st coat	15m2	.6	
1.4	Duromastic PUM 2nd coat	15m2	1.0	
1.5	Duroseal 25LM joint sealant	15x15mm	15mm	15years
2	Internal Above screed			
2.1	WBE hibuild epoxy primer 1st coat	80m2	.3	
2.3	Duromastic p15 1st coat	7.5m2	1.0	
2.4	Duromastic p15 2nd coat	7.5m2	1.0	
2.5	Duroseal 25LM joint sealant	15x15mm	15mm	15years
3	Balconies Below Screed			
3.1	WBE hibuild epoxy primer 1st coat	80m2	.3	
3.2	Duromastic PUM 1st coat	10m2	.6	
3.3	Duromastic PUM 2nd coat	10m2	.6	
3.4	Duroseal 25LM joint sealant	15x15mm	15mm	20years
4	External Balcony Below PODS			
4.1	WBE hibuild epoxy primer 1st coat	80m2	.3	
4.2	Duromastic PPM 1st coat	10m2	1.0	
4.3	Duromastic PPM 2nd coat	10m2	1.0	
4.4	Duroseal 25LM joint sealant	15x15mm	15mm	20years
5	Planter Boxes			
5.1	Bitumen Primer	80m2	.3	
5.2	#mm base sheet	10m2	1.0	
5.3	4mm anti root sheet	10m2	1.0	
7	Roof Top non exposed			
7.1	WBE hibuild epoxy primer 1st coat	80m2	.3	
7.2	Duromastic PPM 1st coat	10m2	1.0	
7.3	Duromastic PPM 2nd coat	10m2	1.0	
7.4	Duroseal 25LM joint sealant	15x15mm	15mm	20years

Comment:

1. Areas are to be flood tested by waterproofing contractor and building contractor
2. Film thickness testing required samples to be submitted by waterproofing contractor

DUROTECH INDUSTRIES

"This document, including any attached files, is strictly confidential and intended solely for the use of the individual or entity to which it is addressed. Durotech Industries prohibits the right to publish, copy, distribute or disclose any information contained in this document, or its attachments, by any party other than the intended recipient. If you have received this document in error please notify the sender and delete it from your system immediately. no employee or agent is authorised to conclude any binding agreement or make any representation on behalf of Durotech Industries. The views or opinions presented in this document are solely those of the author and do not necessarily represent those of Durotech Industries, except where the sender expressly, and with clear authority, states them to be the views of Durotech Industries. Durotech Industries accepts no liability for any loss or damage (direct or indirect or consequential) arising from the use of or in connection with this document and any attacchments and suggests that the recipient check this document and any attached files for the presence of viruses."

JAS-ANZ ©

ISO 9001 Quality Certified System

ISO 14001 Environment Certified System

ISO 45001 Health and Safety Certified System